




ISSN: 2640-9690



***Corresponding author:** Lívia Mačák*,
Institute of Materials and Quality
Engineering, Faculty of Materials
Metallurgy and Recycling, Technical
University of Košice, Letná, Slovakia

Submission:  March 26, 2024

Published:  April 08, 2024

Volume 5 - Issue 3

How to cite this article: Lívia Mačák*,
Oksana Velgosova and Elena Čižmarová.
Synthesis of Differently Shaped
Nontoxic AgNPs Stabilized by PVP
and TSC. *Evolutions Mech Eng.* 5(3).
EME.000612. 2024.
DOI: [10.31031/EME.2024.05.000612](https://doi.org/10.31031/EME.2024.05.000612)

Copyright@ Lívia Mačák, This article is
distributed under the terms of the Creative
Commons Attribution 4.0 International
License, which permits unrestricted use
and redistribution provided that the
original author and source are credited.

Synthesis of Differently Shaped Nontoxic AgNPs Stabilized by PVP and TSC

Lívia Mačák^{1*}, Oksana Velgosova¹ and Elena Čižmarová²

¹Institute of Materials and Quality Engineering, Faculty of Materials Metallurgy and Recycling, Technical University of Košice, Letná, Slovakia

²Department of Materials Engineering, Faculty of Mechanical Engineering, Czech Technical University in Prague, Czech Republic

Abstract

Adjusting the shape of nanoparticles is a fundamental issue in achieving the desired properties. We have proven that it is possible to synthesize the nanoparticles with the desired shapes (spherical, triangular, and colloids with a mixture of shapes) by a suitable combination of reagents. Subsequently, the size and shape of the nanoparticles affect the color of the solution. UV-VIS spectroscopy was used to evaluate the colloidal solutions, and Transmission Electron Microscopy (TEM) to indicate the shape and size of the nanoparticles. Combination of electrostatic repulsion (TCS) and steric stabilization (PVP) secure stability of nanoparticles and act also as good capping agents. AgNPs show very low antimicrobial/antibiofilm activity against *Escherichia coli* (*E. coli*) and *Staphylococcus aureus* (*S. aureus*) bacteria and one-cell algae *Chlorella kessleri* (*Ch. kessleri*).

Keywords: Silver nanoparticles; Chemical synthesis; UV-VIS spectroscopy; TEM; Toxicity

Introduction

Silver nanoparticles are used in various fields such as electronics, healthcare and consumer products. The healthcare industry is the second significant consumer of AgNPs, where nanoparticles are used in medical devices, wound dressings and other applications. There are several methods of nanoparticle synthesis. One of the simplest is chemical, this procedure involves reduction reactions in a metal precursor solution. The precursor ions are reduced using suitable reducing agents and the addition of stabilizing agents ensures the stability of the nanoparticles. By changing the reagents' concentration and other processing conditions it is possible to prepare nanoparticles with different shapes. The shape of the silver nanoparticles is an important factor in determining the optical properties of the colloid and can be tuned to produce a wide range of colors. The shape of AgNPs has important implications for a variety of applications including sensing, imaging and catalysis [1,2]. The shape of AgNPs also impact their interaction with biological systems. V práci Auclair a kol. sledovali úroveň toxicity nanočastíc striebra v závislosti od ich tvaru. Zistili že najvyšiu toxicitu vykazuje iónové striebro, potom sférické nanočastice a nakoniec kubicko-prizmatické nanočastice [3]. Silver is well known for its toxic properties but in some applications, it is needed to suppress this property. Nontoxic AgNPs can find applications in medicine, can be functionalized, or loaded with various active ingredients such as drugs, antimicrobial agents. Non-toxic AgNPs allow controlled and targeted release of these substances, ensuring effective delivery while minimizing potential toxicity to healthy cells. Overall, the need for different shapes of AgNPs arises from the desire to tailor their properties to specific applications. The aim of this work was to develop an easy technique to synthesize silver nanoparticles of different shapes. We analyzed the impact of NaBH₄ volume on shape formation and proved the PVP and TSC capability to ensure a good capping/stabilizing effect of prepared nanoparticles. The toxic tests were performed on bacteria *E. coli*, *S. aureus* and one-cell algal *Ch. kessleri*.

Materials and Methods

Silver nitrate (>98%), sodium borohydride ($\geq 98\%$), sodium citrate (TSC) ($\geq 99\%$), hydrogen peroxide (30%) and Polyvinylpyrrolidone (PVP) were purchased from Mikrochem Ltd., Pezinok, Slovakia. De-ionized water was used for preparing all solutions. Silver nanoparticles were synthesized by chemical method, the concentration and volume of used solutions were as follow: AgNO_3 -0.11mM, 100ml; TSC-30mM, 8.56ml; PVP-2% w/w, 8.56ml; H_2O_2 -30%, 0.28ml; NaBH_4 -0.1M, different volumes: 0.35, 0.37, 0.4, 0.47, 0.58 and 0.7ml. All reagents were freshly prepared and in 1min intervals, added to AgNO_3 solution under constant steering in followed order (except sample Ag4): TSC, PVP, H_2O_2 and NaBH_4 . Subsequently, solutions were covered and stirred for 25min in the dark. The labeling of solutions: Ag1, Ag2, Ag3, Ag5 and Ag6- all reagents added, volume of NaBH_4 0.35, 0.37, 0.4, 0.58 and 0.7ml, respectively. Ag4 was prepared similarly but without TSC, and H_2O_2 was added, volume of NaBH_4 was 0.47ml. Synthesized AgNPs were analyzed by UNICAM UV-VIS Spectrophotometer UV4. The size and morphology of the nanoparticles were studied by means of TEM (JEOL model JEM-2000FX). The image analysis (Image J software) was used for the analysis of Ag nanoparticles' size.

Toxicity

The toxicity of colloidal AgNPs was evaluated using the agar well diffusion and the standard disk-diffusion method. Three microorganisms were used for testing: *E. coli*, *S. aureus*, and *Ch. kessleri*. In agar disk-diffusion test, agar plates were inoculated with the microorganism *Ch. kessleri*. Then, sterile swabs ($\phi 6\text{mm}$) containing the test compound ($\sim 15\mu\text{l}$) were placed on the agar surface. The agar well diffusion method was performed on bacteria

E. coli and *S. aureus*. The agar plate surface was inoculated by spreading the microbial inoculum over the agar surface. Then, a hole with a diameter of 6mm was aseptically punched, and a volume ($20\mu\text{L}$) of the tested agent was introduced into the well. In both tests, Petri dishes were incubated under suitable conditions and the diameters of inhibition zones were measured. As a control, the AgNO_3 solution was used.

Result and Discussion

After adding all the ingredients and stirring for 25 minutes in the dark, colloids of different colors were formed, Figure 1, which indicates the presence of differently shaped nanoparticles. Based on the UV-VIS spectra, Figure 1a)-f), it is possible to divide all colloids into three groups: solutions with one (Ag4), three (Ag1, Ag3, Ag5, Ag6) and four peaks (Ag2). The TEM micrographs of AgNPs colloids are in Figure 1g)-l). Regarding UV-VIS spectra and TEM analysis, it can be concluded that all colloids, where spectra show a peak near 400nm contain spherical nanoparticles, Table 1. It is obvious that in all solutions that have a peak above 500nm the presence of triangles nano-prisms was observed. The higher the value of the peak wavelength, the greater portion of triangular prisms in the colloid. If there is a significant peak at $\sim 500\text{nm}$, rods may be synthesized, but this peak must be perceived in combination with other peaks, especially with a peak at higher wavelengths. The more the maxima are shifted to higher wavelengths, the sharper the triangles [4]. There are many works dealing with the effect of nanoparticle shape on toxicity and with the main mechanisms of AgNPs toxicity on living cells [5]. Nanoparticles can have a toxic effect on the cell through three mechanisms: oxidative stress, DNA damage, and reproductive disorders.




Figure 1: UV-VIS spectra and TEM micrographs of colloids. Sample: Ag1 to Ag6 corresponds to g)-l) microphotographs.

Table 1: Comparison of peaks wavelength and AgNPs shapes.

Peak Number	Sample	Peaks Wavelength (nm)				AgNPs Shape and Size(nm)		
						Spheres	Rods	Triangular
1	Ag4		406			12nm		
3	Ag1	334	400		552	8nm	24nm	truncated 25nm
	Ag3	332		484	658		30nm	30nm
	Ag5	334	390		612	10nm		44nm
	Ag6	330			556			30-12nm
4	Ag2	332	392	484	772	10nm	33nm	40nm

The degree of antibiofilm/toxic effect of prepared AgNPs on *Ch. kessleri* is shown in Figure 2. After 14 days of cultivation, just a very low, negligible inhibition zones were observed for colloid samples. Inhibition zones were max 9mm in diameter, which can be considered as a negligible toxic effect. On the other hand, AgNO_3

control showed a 12mm inhibition zone, which proved that Ag^+ ions have a good toxic effect. No inhibition zones were observed at the agar well diffusion method performed on *E. coli* and *S. aureus* (data not shown).



Figure 2: The anti-biofilm effect of AgNPs colloids and AgNO_3 solution.

With proper AgNPs stabilization [6] there is a low probability of Ag^+ ions release from AgNPs. Among the most common stabilization agents belong polymers, such as polyvinylpyrrolidone, polyethylene glycol, thiol-capping agents, etc. Surface coatings of nanoparticles are used mainly to stabilize them and prevent them from aggregating, it also reduces their toxicity by preventing them from interacting with biological molecules. The choice of surface coating depends on the specific application and the desired properties of the nanoparticles. TSC is mainly a stabilization agent, Gontijo LAP et al. [7] report that the silver colloidal particles possessed a negative charge due to the

adsorbed citrate ions, a repulsive force worked along particles and prevented aggregation [7] (electrostatic repulsion), Figure 3. The latest research shows that citrate ions alone can stabilize the silver nanoplates by stabilizing formed silver nuclei through preferential binding to the {111} planes [8]. But its stabilization effect must be supported by another ligand. The combination of citrate and PVP helps to stabilize and control the formation of nanoparticles shape. PVP provides covalent organic ligands and allows steric repulsion to prevent aggregation, moreover, it can protect AgNPs surfaces from oxidation and instability [9].




Figure 3: Scheme of AgNPs synthesis and stabilization by TSC and PVP.

PVP has a higher affinity for the AgNPs surface than TSC. Citrate is generally thought to be weakly bound to the surface. In contrast, PVP coordinates with the AgNPs surface through van der Waals interactions and direct bonding interactions with the Ag d-band [10]. Due to direct bonding interactions, PVP is more complicated to displace than citrate. Studies have also shown that AgNPs exhibit dose-dependent toxicity, increasing their toxicity with increasing concentrations. The reason why our AgNPs are not highly toxic is that they have low solubility in water because of the good coating/stabilizing effect (PVP and TSC). The exact mechanisms underlying the toxicity of AgNPs are still not fully understood. The concentration and stabilization of AgNPs surface are key factors but it was found that the shape of AgNPs is also one of the important factors [3]. Some shapes are more toxic than others. Spherical

AgNPs have been shown to have lower toxicity compared to other shapes. The reason is that spherical AgNPs have a lower surface-to-volume ratio - **to another shapes**, which reduces their ability to interact with biological molecules and cells. AgNPs of other shapes such as truncated triangles were found to be more toxic than spherical ones. Triangular AgNPs have been found to be the most toxic shape. This is thought to be because the sharp edges and corners of the triangles can cause physical damage to cells and tissues. Also, the release of silver ions from triangular corners is more likely than from the surface of spherical nanoparticles.

Conclusion

We successfully prepared differently shaped silver nanoparticles by changing the concentration of the main reducing agent. The shape of nanoparticles influenced the color of the

colloidal solution. It was proved that despite the toxicity of silver nanoparticles the use of PVP and TSC as stabilizing/capping agents secured the nontoxicity of synthesized AgNPs regardless of their shape. The proper coating increases the application possibility of nanoparticles.

Acknowledgment

This work was financially supported by Slovak Grant Agency (VEGA 1/0020/22).

References

1. Kelly KL, Coronado E, Zhao LL, Schatz GC (2003) The optical properties of metal nanoparticles: The influence of size, shape, and dielectric environment. *The Journal of Physical Chemistry B* 107: 668-677.
2. Hutter E, Fendler JH (2004) Exploitation of localized surface plasmon resonance. *Advanced Materials* 16: 1685-1706.
3. Auclair J, Gagné F (2022) Shape dependent toxicity of silver nanoparticles on freshwater cnidarians. *Nanomaterials (Basel)* 12(18): 3107.
4. Raza M, Kanwal Z, Rauf A, Sabri A, Riaz S, et al. (2016) Size and shape-dependent antibacterial studies of silver nanoparticles synthesized by wet chemical routes. *Nanomaterials* 6(4): 74.
5. Stensberg MC, Wei Q, McLamore ES, Porterfield DM, Wei A, et al. (2011) Toxicological studies on silver nanoparticles: Challenges and opportunities in assessment, monitoring and imaging. *Nanomedicine* 6(5): 879-898.
6. Majeed S, Aripin FHB, Shueb NSB, Danish M, Ibrahim MNM, et al. (2019) Bioengineered silver nanoparticles capped with bovine serum albumin and its anticancer and apoptotic activity against breast, bone and intestinal colon cancer cell lines. *Mat Sci Eng C* 102: 254-263.
7. Gontijo LAP, Raphael E, Ferrari D, Ferrari JL, Lyon J, et al. (2020) PH effect on the synthesis of different size silver nanoparticles evaluated by DLS and their size-dependent antimicrobial activity. *Rev Matéria* 25(4): e12845.
8. Zhang Q, Li N, Goebel J, Lu Z, Yin Y (2011) Systematic study of the synthesis of silver nanoplates: Is citrate a "magic" reagent? *J Am Chem Soc* 133(46): 18931-18939.
9. Miesen TJ, Engstrom AM, Frost DC (2020) A hybrid lipid membrane coating "shape-locks" silver nanoparticles to prevent surface oxidation and silver ion dissolution. *RSC Adv* 10(27): 15677-15693.
10. Jacobson KH, Gunsolus IL, Kuech TR, Troiano JM, Melby ES, et al. (2015) Lipopolysaccharide density and structure govern the extent and distance of nanoparticle interaction with actual and model bacterial outer membranes. *Environmental Science & Technology* 49(17): 10642-10650.